

SURVEY & REMONUMENTATION

1994 ALPENA COUNTY REMONUMENTATION CORNER

APR 06 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

007641

RECORDED
ALPENA COUNTY MI.

LIBER 1 PAGE 350
DEC 29 2 21 PM '94

Myriam A. Johnston
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Alpena

(County)

Located In:

Corner Code ~~##~~

- | | | |
|------------------------------------|------------|------|
| 1. Public Land Survey | T 30N R 7E | G-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous | S T R | |
| Property in Sec. | S T R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Duane R. MacNeill, in a field survey on May 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A Description of original monument and accessories and/or subsequent restoration:

1839 - Cedar post set by Thad Pattison, D.S.

1915 - Joseph McNeil found evidence of original corner, but did not state what was found or what was set.

Witnesses:

Tam 16" N33°E 34
Tam 24" S08°W 22

No Witnesses Supplied

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1982 - Alpena County Road Commission Surveyor found concrete monument (unknown origin) after Road Construction complete, raised with a 1/2" re-rod.

1984 - D.R. MacNeill & Associates find 1/2" re-rod in monument box.

Witnesses:

West 49.35 Nail in Fence Corner
S60°E 58.33 Nail in Power Pole
N30°W 112.44 Second Steel Fence Post.

No Witnessess Supplied

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


1994 Remonumentation Crew found 1/2" re-rod in Monument box. An Alpena County Aluminum Remonumentation Cap, appropriately stamped, was secured to the existing 1/2" re-rod.

P.A. 345 ALPENA COUNTY
PEER APPROVED 12-15-94
D.R. MacNeill

Witnesses:

N80°E 66.49 Stop sign
S70°E 56.69 P.P.
S70°W 54.31 Guy Pole
Due West 49.30 Fence Corner

Signed by



Surveyor's Michigan License No. 19237

Date

12/28/94