

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF:-   | LOCATED IN:- | CORNER CODE NUMBER |
|--|--------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>5</u> T. <u>30</u> N. <u>8</u> R. <u>8</u> E. <u>W</u>              |              | <u>C-1; E-2;</u>   |
| 2. PROPERTY CONTROLLING IN SECTION <u>5</u> T. <u>30</u> N. <u>8</u> R. <u>8</u> E. <u>W</u> |              | <u>3</u>           |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ R. _____ E. _____               |              |                    |
| 4. LOT NO. _____, RECORDED PLAT _____  |              |                    |
| 5. PRIVATE CLAIMS _____  |              |                    |

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on February 12, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

See Continued

A. ~~Description of monument and accessories established to perpetuate locating the position of the corner:~~

E-2

Set D.N.R. mon. and cedar post  
8" R. Pine S35°E 159.9'  
2" Maple N35°E 18.2'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Set corner proportionately on line between found 1/4 corner and section corner.  
C-1 Set corner at found 1 1/2" pipe in concrete set by Marcus Schaaf in a 1919 survey.  
E-2 Set corner proportionately on line with found recorded section corner to South, and closing corner to North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3  
Set 5/8" bar w/cap and cedar post  
7" Maple N73°W 27.9'  
10" Maple S63°W 30.9'  
1" Pipe N79°W 16.43'  
1 1/2" Pipe in Conc. S5°W 12.75'

C-1  
Set D.N.R. mon. and cedar post  
7" R. Pine S76°E 48.1'  
6" W. Pine S62°W 74.8'  
2 ft South of E - W Fence

SIGNED BY

*Carl R. Johnson*

DATE

4/2/86

SURVEYOR'S MICHIGAN REGISTRATION NO. 30083

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE


CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY

DATE

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Alpena County