

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32N R 06E

D-7

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 6-01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856: Josiah Knauer reestablished old post and witnessed
1901: Wm. H. Leroy set Cedar stake, 3" square, and witnessed
1905: Wm. H. Leroy used corner, no monumentation or witnesses given
1997: W. T. Lewis, P.S., set 1/2" rerod w/cap in place of exist. pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod w/cap #41922 in Greenwood Road C/L and in line w/fence to the South

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alpena County Cap, stamped to identify the corner, on existing 1/2" rerod, 6" below road surface

Witnesses:

North 30.32' 12" Cedar (Fd. Tag #41922)
N 45° E 58.30' 6" Apple (Fd. Tag #41922)
S 10° E 37.15' Power Pole (Fd. Tag #41922)
S 80° W 128.84' 12" Elm

Signed by

Wayne T. Lewis

Surveyor's Michigan License No.

41922

Date November 24, 1999

RECORDED


JAN 21 2000

SECTION

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99
D.D.R.



L-2 P-255
11/30/1999 03:30P
Page: 1 of 1
MI LDC 9.00

Kathy J. Matash, Register Alpena Co., MI

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995