

1999 Alpena County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alpena

(County)

Located In:

Corner Code #

1. Public Land Survey

T 32NR 06E

G-11

2. Property Controlling
in Section

S

T

R

3. Miscellaneous
Property in Sec.

S

T

R

S

T

R

S

T

R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

RECORDED

JAN 21, 2000

SECTION

I, Wayne T. Lewis, in a field survey on 6-01, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856: Josiah Knauer set post and witnessed

1893: Wm. H. Leroy found corner, set limestone, no witnesses given

1889: Wm. H. Leroy found corner, no monumentation or witnesses given

1904: J. McNeil found stone in cross roads, no witnesses given

1958: MDOT Surveyor found 1-1/4" pipe, and witnessed

Unknown date: Alpena County Road Commission Field Notes, found 1-1/2" pipe, no witnesses given

1999: W. T. Lewis, P.S., found 1" pipe 3' West of N/S C/L, and 5' South of West C/L, and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe 3' West of Keating Rd. C/L, and in MacArthur Rd. C/L

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1999: Placed 3" Alpena County Cap, stamped to identify the corner, on 1/2" rerod driven next to pipe

Witnesses:

N 45° E 52.60' 5" Spruce (Fd. Tag #41922)

S 45° E 37.55' 15" Spruce (Fd. Tag #41922)

S 30° E 89.94' Power Pole (Fd. Tag #41922)

S 45° W 61.15' Power Pole (Fd. Tag #41922)

S 20° E 70.47' 36" Elm

S 80° W 82.76' Top Center 32" Elm Stump


Signed by [Signature]

Surveyor's Michigan License No. 41922

Date November 24, 1999

P.A. 345 ALPENA COUNTY
PEER APPROVED 9/16/99

[Signature]



L-2 P-253

11/30/1999 03:30P

Page: 1 of 1

Kathy J. Matash, Register Alpena Co., MI LDC 9.00

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985