

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 33W	F3
	T 47N R 33W	G4
2. Property Controlling in Section	T	R
	T	R
	T	R
3. Miscellaneous Property in Sec.	S	T
	S	T
	S	T
	S	T
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						9		10		11		12	
4	7		8										
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on F3 08/23/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F3) Quarter corner common to Sections 4 and 9. 1852 - Established by Deputy Surveyor Francis Houck
midway and on the Section line between Section corners 39.965 chains east and west. Set post. Cedar
8 N48E 13 links, Y.Birch 8 S11W 21 links. Found no subsequent record.

(G4) Quarter corner common to Sections 9 and 10. 1852 - Established by Deputy Surveyor Francis Houck
midway and on the Section line between Section corners 40.00 chains north and south. Cedar 4" for
1/4 corner. Cedar 8 N60W 22 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F3) The original post and accessories were not recovered. There are many old cedar stumps in the
area and remains of a few Y.Birch trees but none were found to match the record. Found no evidence
of the position of the original corner on the ground. Reestablished the position for the corner
midway and on the Section line between Section corners 2635.92 ft. east and west.

(G4) The original corner tree and accessory were not recovered. No cedar stumps are present in this
area. Found no evidence of the position of the original corner on the ground. Reestablished the
position for the corner midway and on the Section line between Section corners 2628.73 feet north and
south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
made firm with 5 cedar hubs, driven adjacent.
Set measuring nail with MDNR tag in the side of:
4" Cedar N42E 7.7' mrkd "1/4S NBT"
7" Cedar S13E 14.8' do
3" Cedar S52W 1.15' do
5" Tamarack N49W 9.7' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(G4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Y.Birch N26E 13.0' mrkd "1/4S NBT"
11" Maple S49E 18.3' do
3" Spruce S14W 4.25' do
11" Maple N21W 13.4' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 04/26/2012

For the Michigan Department of Natural Resources, Forest Resources Division

