

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 33W	G3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/18/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1852 - Established by Deputy Surveyor Francis Houck.  
"Corner of Sections 3-4-9 & 10 Cedar 12 N74E 21 links, Cedar 10 S16W 25 links." 2003 - Mead Corp.  
records (undated) show old Cedar NE BT found. Set post/tag.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Found Cedar post approx. 15-20 years old with remains of two older posts at its base, both now  
3" dia. post points 12"-18" long, adjacent, rotted off at the level of the water table. At record  
bearing and distance from the points, recovered the rotted remains of the probable BT Cedar N74E 21  
links, mostly down and rotting with deteriorating upper and lower blazes. No scribing found.  
Accepted the post points as a careful and faithful perpetuation of the position of the original  
corner, one of which may be the remains of the original post. No trace of the SW BT Cedar found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Set 1"IDx32" I.pipe with plastic MDNR cap  
Set measuring nail with MDNR tag in the side of:  
9" Cedar S42E 22.0' mrkd "S10 NBT"  
8" Cedar S09W 35.5' "S9 NBT"  
4" B.Spruce S89W 9.2' "S9 NBT"  
12" Cedar N79W 10.8' "S4 NBT"  
Set sq'd cedar post adjacent.  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 04/26/2012

For the Michigan Department of Natural Resources, Forest Resources Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971