

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 31W	G4
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 10 T 48N R 31W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

I, Stephan J. Szyszkoski, in a field survey on 3 05/10/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G4) Quarter corner common to Sections 9 and 10. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set cedar post. Cedar 12 S51W 42 links, W.Pine 24 North 5 links.

(3-Sec. 10) North 1/16 corner between Sections 9 and 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2614.12' north and south, proportionate to the original record. The position for the corner falls on exposed granite. The monument is a 1"IDx10" iron pipe with 4" alum. MDNR cap with a 5/8"x9" rebar grouted inside, which rebar is grouted into a 3/4"x4" deep hole drilled into the granite.

(3-Sec. 10) Established the corner midway and on the Section line between Section corner 1307.06' north and Quarter corner 1307.06' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G4) Set 1" capped pipe as described in Part B. Set measuring nail with MDNR tag in the side of:  
5" Maple N10E 6.9' mrkd "1/4S NBT"  
4" Y.Birch S08W 2.2' do  
5" Maple S67W 11.8' do  
3" twin Hemlock N72W 17.75' do  
Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
8" Maple N02W 7.5' mrkd "1/16S BT"  
3" Balsam N49E 5.7' do  
9" Maple S23E 11.25' do  
5" Balsam S19W 1.2' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/07/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

