

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 10 T 48N R 32W	14 (GCDB 500520)
	S 9 T 48N R 32W	5 (GCDB 340560)
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 06/03/14
14 06/02/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 10) South 1/16 corner between Sections 10 and 11. 1970 - Established by A.O. Enger RLS
midway and on line between Section corner 19.891 ch. South and 1/4 corner 19.891 ch. North. Set
1"IDx36" I.pipe with 4" alum. cap. W.Spruce 9" N32°E 13.7', B.Spruce 6" S64°W 13.0'.

(5-Sec. 9) Center-North 1/16 corner, Section 9. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 10) Found the 1970 monument in good condition and at record bearing and distance from the
remaining 1970 BT Spruce N32°E 13.7', found with blazes overgrown. Found the monument to be
substantially at the position of record and accepted same as a careful and faithful establishment of
the position of the corner.

(5-Sec. 9) Established the position for the corner midway and on a straight line between Quarter
corner 1310.42' north and the intersection of 1/4 lines of Section 9 1310.42' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Found 1"ID I.pipe with 4" alum. MI Dept. of
Conservation cap. Set measuring nail with MDNR tag
in the side of:
Spruce N36°E 14.5' old blazes (1970 BT)
7" B.Spruce S77°E 6.8' mrkd "1/16S BT"
4" B.Spruce S38°W 11.25' do
6" Balsam N76°W 8.1' do
Set sq'd cedar post adjacent.
E= 7901651.086 N= 199111.250

(5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" B.Spruce N22°E 4.75' mrkd "1/16S BT"
3" Tamarack S33°E 10.1' do
3" Spruce S60°W 9.4' do
7" B.Spruce N41°W 13.75' do
Set sq'd cedar post adjacent.
E= 7899248.993 N= 199960.807

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID RL1468: N= 199449.721 m. E= 7900600.011 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 06/18/2014

For the Michigan Department of Natural Resources, Forest Resources Division

