

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	E5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 16 T 48N R 33W	F6
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E5 09/15/2010 F6 09/21/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E5) Corner common to Sections 8-9-16-17. 1992 - Reestablished by K.L.Sackett RLS by proportionate measurement. Set 1"IDx32" I.pipe with plastic cap. 12" Tamarack N83E 84.0', 14" Balsam S43E 79.7', 8" Balsam S21W 46.1'.

(F6) Center of Section 16. 1992 - Established by K.L.Sackett RLS at the intersection of 1/4 lines. Set 1"IDx32" I.pipe with 4" alum. cap. 5" Balsam S83E 2.6', 5" Spruce N32W 17.4', 4" Balsam N65E 19.8', 5" Spruce S03W 17.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E5) Found the 1992 monument in good condition and at record bearing and distance from the three 1992 NBTs, all standing dead with scribing visible. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(F6) Found the 1992 monument in good condition and at the record position. None of the 1992 witnesses were recovered. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E5) Found 1"ID I.pipe with plastic cap #19006
Set measuring nail with MDNR tag in the side of:
7" Tamarack N34W 52.15' mrkd "S8 NBT"
7" Tamarack N54E 35.6' "S9 NBT"
7" Tamarack N73E 37.45' do
5" Maple S22E 43.9' "S16 NBT"
Fd. sq'd tamarack post adjacent.
Bearings are magnetic.

(F6) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Spruce N10E 37.85' mrkd "C1/4 BT"
9" Spruce S12W 20.25' do
13" Spruce S78W 30.45' do
3" Maple N47W 4.75' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/12/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

