

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 34W	D9
	T R	
	T R	
2. Property Controlling in Section	S 29 T 49N R 34W	4
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10/29/12 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4) Northwest 1/16 corner, Section 29. Not previously monumented.

(D9) Quarter corner common to Sections 20 and 29. 1959 - Billy D. Buckler RLS reestablished the corner
position midway and on line between Section corners. No original evidence. Set 1" pipe with 4"
brass cap. 6" J.Pine S62E 08 links, 6" J.Pine N38E 14 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4) Established the position for the corner at the intersection of straight lines connecting
opposite 1/16 corners.

(D9) Found the 1959 monument in good condition. Nothing remains of the 1959 NBTs. I note that the
1959 survey is characterized by rather loose measurements. This monument is situated S54W 8.8' from
the position intended in 1959. Given that the monument is of long standing and has been used on
subsequent surveys, I accept it as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" J.Pine N82°E 16.7' mrkd "1/16S BT"
4" J.Pine S25°E 21.55' do
5" J.Pine S77°W 12.35' do
4" J.Pine N48°W 8.95' do
4"x4" treated wood post adjacent.
E=7878223.073 N=205172.016

(D9) Found 1"ID I.pipe with 4" brass MI. Dept. of
Conservation cap. Set measuring nail with MDNR
tag in the side of:
8" J.Pine N17°E 8.6' mrkd "1/4S NBT"
5" J.Pine S75°E 26.65' do
5" J.Pine S14°E 13.95' do
6" J.Pine S80°W 11.7' do
E=7878631.738 N=205561.523

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/13/2013

For the Michigan Department of Natural Resources, Forest Resources Division

