

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 34W	I8
	T R	
	T R	
2. Property Controlling in Section	S 28 T 49N R 34W	9
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11/29/12 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I8) **Quarter corner common to Sections 22 and 23.** 1972 - A.O.Enger RLS reestablished the position for the corner midway and on the Section line between Section corners 39.70 chains north and south. Set 1"IDx36" I.pipe with 4" alum. cap. Cedar 10" S71°W 38.0', Cedar 6" N30 1/2°W 28.4'.

(9) **East 1/16 corner, Section 28.** 1975 - Established in 1975 by K.L.Sackett RLS. Method not described. Set 1"IDx36" I.pipe with 4" aluminum cap. 8" J.Pine N66E 4.0', 7" J.Pine N82W 12.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I8) Found the 1972 monument in good condition and at record bearing and distance from the 1972 accessories. The Cedar S71°W is in good condition with scribing visible. The Cedar N30 1/2°W is in good condition but without visible marks. The monument is substantially at the record position with respect to Section corners north and south and I accept same as a careful and faithful reestablishment of the position of the original corner.

(9) Found the 1972 monument 19.34' west of the proper position for the corner and removed it. Established the position for the corner midway and on a straight line between Center of Section 1324.58' west and Quarter corner 1324.58' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I8) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
11" Cedar S74°W 38.0' old scribing (1972 NBT)
9" Cedar N26°W 28.4' mrkd "1/4S NBT"
7" Cedar S53°E 20.45' do
9" Cedar S16°W 8.85' do
Set sq'd cedar post adjacent.
E=7882672.286 N=206268.025

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
4" Spruce S76°E 21.75' mrkd "1/16S BT"
12" R.Pine S27°E 46.35' do
12" J.Pine S35°W 37.6' do
10" J.Pine N79°W 15.4' do
Set sq'd cedar post adjacent.
E=7880618.516 N=204713.151

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/13/2013

For the Michigan Department of Natural Resources, Forest Resources Division



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1983

Revised Oct., 1995