LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

5. Private Claims

Baraga	Located In:	Corner Code #
(County)	- 12	
1. Public Land Survey	TR TR	
2. Property Controlling in Section	S 36 T 49N R 33W S T R R S 36 T 49N R 33W	12 (GCDB 640120) L12
3. Miscellaneous Property in Sec.	S T R	(GCDB 640140)
4. Lot No. Rec	corded Plat	

Register of Deeds Stamp & File Number

OF MICH


STEPHAN J

SZYSZKOSKI LAND SURVEYOR


12

Stephan J. Szyszkoski , in a field survey on 09/02/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 re-established, monumented, recovered, found as expressed below:

above were in conformance with regulations and rules therefore as required in the current manual of survey 5 instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of 6 a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with 7 the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, 8 9 10 NOTE: Not more than 2 corners, all in the same town and range, may be recorded 11 on this certificate.



(12-Sec. 36) Center-South 1/16 corner, Section 36. Not previously monumented.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

corner 1314.38' south and the Center of Section 36 1314.38' north.

(12-Sec. 36) Established the position for the corner midway and on a straight line between Quarter

(L12) Established the position for the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. (L12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: Set measuring nail with MDNR tag in the side of: 5" Sugar N23°E 12.9' mrkd "1/16S BT" 10" dbl Cherry N24°E 16.25' mrkd "C1/4 BT" 5" Y.Birch S84°E 13.0' do 10" Cherry N80°E 23.6' do 6" Sugar S27°E 23.8' do 10" Y.Birch S45°W 38.2' đо 2" Balsam S79°W 5.45' 6" dbl Cherry N63°W 17.55' do Set sq'd cedar post adjacent. Set sq'd cedar post adjacent. E= 7894562.819 N= 202431.169 E= 7894566.929 N= 202831.707

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum. Coord. Ref.=NGS PID RL0476: N= 196482.411 m. E=7879234.516 m.

Signed by Stephen Kynsylle	shi	Date	10/27/2015	
Surveyor's Michigan License No.	33986	-		