

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 33W

I12

T 49N R 33W

G13

T R

S T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

G13 Oct 18 2005

I12 Oct 13 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I12) Quarter corner common to Sections 34 & 35. 1852 - Established by Zelotes B. Searles, Deputy Surveyor: "N3'W corrected between sections 34 & 35. ...39.98 Set quarter section post. Fir 10 S53W 15 links, Fir 10 N50E 26 links. ...79.96 set post corner of sections 26-27-34-35". Circa 1948 - Notes of N.T.Thompson, RLS, found at Northern Hardwoods office in Bovine, MI state that Fir BTs are "gone" and that "New B.T. Cedar 8 S50W 25'6", and Cedar 5 S10E 20'."

(G13) Corner common to Section 33-34 T49N-R33W and Sections 3-4 T48N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor: "West on south side of Section 34 ...80.00 Set spruce post corner of Sections 33-34. Spruce 12 N53E 13 links, Cedar 10 N70W 3 links". June 30, 1941 - Notes of N.T.Thompson RLS found at Northern Hardwoods office in Bovine, MI state: "New B.T. ced 12 S70W 20 ft., Spr. 16 N27W 8 ft."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(I12) Found a 3/4" ID iron pipe set firm in a 1.5' dia x 1' high rock mound at record bearing and distance from the rotting stump remains of a Cedar S50W 25.5' with no markings visible. The other 1948 NBT was not recovered. Though the GLO position for the corner (midway and on line between section corners) is N46E 34.9' from this position, I accept the pipe as the best available evidence of the position of the original corner.

(G13) The original post and accessories were not recovered. Found a 1 1/2" ID iron pipe, set firm, at record bearing and distance from the 1941 NBT Cedar S70W 20 ft., in good condition with scribing visible on old blazes. The NBT spruce is now a rotting stump at record bearing and distance, with markings visible. Found a 2" sq'd cedar post adjacent. Distances north and east to Quarter corners checks with the original record. Accepted the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I12) Found 3/4" I.pipe in rock mound.
Set measuring nails in:
7" Cherry N20E 71.1' mrkd "1/4S NBT"
7" Maple N46E 67.2' do
10" Spruce S35W 45.9' do
4" Maple in clump S67W 57.2' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(G13) Found a 1 1/2" ID iron pipe. Set measuring nails in:
15" Cedar S72W 21.6' mrkd "S4 NBT" *
6" Cedar S58E 31.2' "S3 NBT"
11" Cedar S24W 28.3' "S4 NBT"
10" Cedar N20W 12.4' "S33 NBT" w/
old Ford Motor tag. Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1941 NBT.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No.

33986

Date

2/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities