

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	C7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/21/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C7) Section corner common to Sections 17-18-19-20. 1849 - Established by Wm.Burt Deputy Surveyor.  
Set Cedar post. Hemlock 16" N29E 26 links, Hemlock 8" S28W 21 links. 1947 - Notes of Norman T.  
Thompson RLS state: "Cor. [at] end of road. Found 2 old post. Set new cedar post. New BT Sug. 8"  
S12E 31.1', Sugar 8" N29E 37.4''; and "Len and Rus chained this mile [C7 to E7] found it to be 5272'.  
Set 1/4 cor. [D7] on prop. [sic] measurement 2636'." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C7) The original post and accessories were not recovered. The N.T.Thompson witnesses of 1947 were  
not recovered. Found an old rotted squared wooden post with location poster affixed, possibly the  
post noted by Thompson, down, out of the ground, obviously disturbed from its original position, not  
accepted by the undersigned, S71W 39' from the position subsequently monumented. I reestablished the  
northing of the corner by proportionate measurement to the original record between corner C4 7890.83'  
north (7920.0' GLO) and corner C9 5260.41' south (5280.0' GLO). I reestablished the easting of the  
corner at index-corrected N.T.Thompson distance west of D7 (2632.57' M, 2636' NTT). From the  
position thus established, the center of a narrow trail running east (likely the "end of road" noted  
in the 1947 notes) is 4' south. I note that the corner position so established is only 2.5' west of  
the position proportionate to the original record measurements between corners A7 and D7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
5" Maple N59E 21.65' mrkd "S17 NBT"  
18" Hemlock S54E 59.6' "S20 NBT"  
5" Sugar S54W 20.8' "S19 NBT"  
4" Y.Birch N15W 22.6' "S18 NBT"  
Set sq'd cedar post adjacent.  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division