

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	C4
	T 50N R 33W	C5
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on C4 08/03/2011 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) Quarter corner common to Sections 7 and 8. 1849 - Established by William Burt Deputy Surveyor on the Section line 40.00 chains north of Section corner and 37.45 chains south of Meander Corner at Keweenaw Bay. Set Hemlock post. Spruce 5" N12W 24 links, Hemlock 18" S38E 34 links. Found no subsequent record.

(C5) Corner common to Sections 7-8-17-18. 1849 - Established by Wm.Burt Deputy Surveyor. Set Hemlock post. Cedar 14" N65W 43 links, Hemlock 10" S68E 21 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) The original post and accessories were not recovered. Found a 1 3/4" dia. iron pin, firmly set, approx. 6" below the ground surface, approx. 14' east of the center of Boyer Road extended southerly, and on the line of a fence to the west, extended easterly. Found a wooden lathe adjacent, marked "W1/4 Sec. 8 50-33". Accepted the pin as the best available evidence of the position of the original corner.

(C5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner by proportionate measurement to the original record measurements between corners C4 2630.41' north (2640.0' GLO), D5 2650.47' east (2653.9' GLO), C9 10520.79' south (10560.0' GLO), and A5 4991.19' west (5004.8' GLO). The position thus established falls on the west edge of a 2-track trail to north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C4) Found 1 3/4" dia. iron pin  
Set measuring nail with MDNR tag in the side of:  
5" Poplar N75E 59.7' mrkd "1/4S NBT"  
4" W.Pine N45W 54.5' do  
Southerly pole of two power poles:  
S57W 42.2' to existing UPEA nail and tag  
Northerly pole of two power poles S70W 36.6'  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(C5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap  
buried to 0.3' below the ground surface.  
Set measuring nail with MDNR tag in the side of:  
5" Maple N70E 31.1' mrkd "S8 NBT"  
11" Hemlock S54E 55.0' "S17 NBT"  
5" Y.Birch N79W 20.7' "S7 NBT"  
5" Ash N21W 33.1' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division

