

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W	F9
	T R	
	T R	
2. Property Controlling in Section	S 34 T 50N R 34W	10
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on F9 06/20/12 10 07/10/12 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F9) Quarter corner common to Sections 21 and 28. 1849 - Established by Wm. Burt Deputy Surveyor midway and on the Section line between Section corners 40.075 chains east and west. Set Hemlock post. Y. Pine 6" S65E 12 links, Maple 8" N72W 12 links.

(10-Sec. 34) South 1/16 corner between Sections 33 and 34. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F9) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2636.00' east and west, being proportionate to the original record.

(10-Sec. 34) Established the position for the corner midway and on the Section line between Section corner 1324.06' south and Quarter corner 1324.06' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
4" Hemlock N85E 6.8' mrkd "1/4S NBT"  
7" Hemlock S08E 8.7' do  
3" Hemlock S75W 8.5' do  
4" Hemlock N37W 7.4' do  
Set sq'd Cedar post adjacent.

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
7" Sugar N77E 18.6' mrkd "1/16S BT"  
15" Sugar S32E 14.3' do  
7" Hemlock N50W 14.7' do  
12" Hemlock N30W 11.5' do  
Set sq'd Cedar post adjacent.

Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/12/2012

For the Michigan Department of Natural Resources, Forest Resources Division

