

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W	E10
	T R	
	T R	
2. Property Controlling in Section	S 34 T 50N R 34W	14
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E10 12/15/11  
14 12/19/11 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E10) Quarter corner common to Sections 28 and 29. 1849 - Established by Wm.Burt Deputy Surveyor  
midway and on the Section line between Section corners 40.00 chains north and south. Set Maple post.  
W.Birch 6" S34E 13 links, W.Birch 6" N75E 22 links. Found no subsequent record.

(14-Sec. 34) South 1/16 corner between Sections 34 and 35. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E10) The original post and accessories were not recovered. Found no evidence of the position of the  
original corner on the ground. Reestablished the position for the corner midway and on the Section  
line between Section corners 2633.87' north and south, being proportionate to the original record.  
The position for the corner falls on a steep north-facing slope.

(14-Sec. 34) Established the position for the corner midway and on the Section line between Quarter  
corner 1316.28' north and Section corner 1316.28' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
12" Twin Oak N50E 15.3' mrkd "1/4S NBT"  
3" Hemlock S67E 1.7' do  
5" Spruce S50W 3.85' do  
6" Hemlock N32W 15.35' do  
Set sq'd cedar post adjacent.

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
7" W.Pine N36E 46.7' mrkd "1/16S BT"  
3" B.Spruce S75E 31.2' do  
2" W.Pine S80W 9.7' mrkd " X X "  
5" W.Pine N09E 45.7' "1/16S BT"  
Set sq'd cedar post adjacent.

Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/12/2012

For the Michigan Department of Natural Resources, Forest Resources Division

