

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W	C6
	T 50N R 34W	B9
2. Property Controlling in Section	T R	
	T R	
	T R	
3. Miscellaneous Property in Sec.	T R	
	T R	
	T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on C6 05/07/13  
B9 05/15/13 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17 and 18. 1961 - Corner remonumented by Billy D. Buckler  
RLS at record bearing and distance from Hemlock BT stump S25°E 21 links. Set 1" pipe with 4" brass  
cap. 9" Hard Maple S15°W 29 links, 9" Y.Birch East 41 links.

(B9) Quarter corner common to Sections 19 and 30. 1849 - Established by Wm. Burt Deputy Surveyor on  
the Section line between Section corners 40.00 chains east and 36.50 chains west. Set Hemlock post.  
Hemlock 6" N30°W 25 links, Hemlock 10" S25°E 37 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) The 1961 monument was not recovered and appears to have been removed at an unknown date by  
earth-moving equipment. Remonumented the 1961 position at substantial record bearing and distance  
from the stump remains of the two 1961 bearing trees and the original BT Hemlock S25°E 21 links.

(B9) The original post and accessories were not recovered. Found no acceptable evidence of the  
position of the original corner on the ground. Reestablished the position for the corner on the  
Section line between Section corners 2637.19' east and 2406.43' west, being proportionate to the  
original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" Spruce N35°W 33.0' mrkd "1/4S NBT"  
3" Oak N88°E 12.75' do  
4" R.Pine S49°E 19.45' do  
5" Sugar S68°W 11.05' do  
Set sq'd cedar post adjacent.  
E= 7878113.096 N= 217571.508

(B9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
7" Oak N43°E 31.9' mrkd "1/4S NBT"  
5" twin Ironwood S69°E 9.4' do  
7" twin Sugar S12°W 6.6' do  
4" W.Birch S82°W 21.25' do  
Set sq'd cedar post adjacent.  
E= 7877245.418 N= 215179.384

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID DI1837: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/02/2013

For the Michigan Department of Natural Resources, Forest Resources Division

