

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W T T	J5 (GCDB 540500)
2. Property Controlling in Section	S 11 T 50N R 34W S S	11 (GCDB 520520)
3. Miscellaneous Property in Sec.	S S S	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on J5 12/07/15 11 12/07/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11 and 14. 1849 - Established by Wm.Burt, Deputy, midway and on the Section line between Section corners 40.22 chains east and west. Set Maple post. Hemlock 15" S20°W 38 links, Y.Birch 10" N45°E 36 links. Found no subsequent record.

(11-Sec. 11) Southwest 1/16 corner, Section 11. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2628.94' east and west.

(11-Sec. 11) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners, those to the north and south being monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
19" Sugar N78°W 25.85' mrkd "1/4S NBT"
9" Sugar S39°E 31.8' do
13" Sugar S65°E 15.5' do
12" Sugar N16°E 34.75' do
Set sq'd cedar post adjacent.
E= 7883735.405 N= 218252.334

(11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
11" Cedar N61°W 40.35' mrkd "1/16S BT"
6" Maple N80°W 35.95' do
6" Maple S06°W 10.75' do
3" Maple S67°E 13.6' do
Set sq'd cedar post adjacent.
E= 7883338.663 N= 218662.510



Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID D08499: N= 221257.621 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/21/2016

For the Michigan Department of Natural Resources, Forest Resources Division