

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 30W	C2
	T R	
	T R	
2. Property Controlling in Section	S 4 T 51N R 30W	7
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		5	6	5		4	3		2		1		
3													
4		7		8		9	10		11		12		
5													
6		18		17		16	15		14		13		
7													
8		19		20		21	22		23		24		
9													
10		30		29		28	27		26		25		
11													
12		31		32		33	34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/12/13 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 4) North 1/16 corner between Sections 3 and 4. Not previously monumented.

(C2) Quarter corner common to Sections 5 and 6. 1965 - Corner remonumented by F.J.Bray RLS from 30"  
W.Pine S78°W 21 links, an original BT, now a 7' high stub with blazes and iron marks on lower face.  
Set 1" iron pipe with 4" aluminum cap. 9" Tamarack S33°E 57.5 links, 30" W.Pine stub (orig. BT)  
S78°W 21 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 4) Established the position for the corner on a straight line between Section corner  
1250.37' north and Quarter corner 1319.70' south, being proportionate to the dimensions given on the  
original plat of this township.

(C2) Found the 1965 monument disturbed, laying nearly horizontally. Removed and reset the monument  
at record bearing and distance from the 1965 witnesses. The Tamarack is in good condition and the  
OBT W.Pine is now a rotted stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx28" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
13" Cedar N02°E 14.65' mrkd "1/16S BT"  
5" Maple N75°E 19.25' do  
14" Cedar N76°W 3.6' do  
4" B.Ash N27°W 19.7' do  
Set sq'd cedar post adjacent.  
E= 7915495.331 N= 230106.433

(C2) Reset 1965 1"ID I.pipe with 4" MI Dept. of  
Conservation cap. Set measuring nail with MDNR  
tag in the side of:  
15" Tamarack S27°E 38.0' old blazes (1965 NBT)  
3" B.Ash S08°E 11.35' mrkd "1/4S NBT"  
4" B.Ash S23°W 22.1' do  
4" B.Ash S72°W 17.55' do  
Set sq'd cedar post adjacent.  
E= 7912284.964 N= 229756.589

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)  
Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.169 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/08/2013

For the Michigan Department of Natural Resources, Forest Resources Division

