

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 31W	K3
	T R	
	T R	
2. Property Controlling in Section	S 1 T 51N R 31W	15
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/10/13 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. 1846 - Established by Hubbard and Ives, Deputy Surveyors.  
Set post. Maple 12" S65°E 15 links, Cedar 8" N26°W 23 links.

(15-Sec. 1) West 1/16 corner between Sections 1 and 12. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) The original post and accessories were not recovered. At the position subsequently monumented,  
I found a 3/4" ID pinched pipe with old signature tree and a 10" Cedar N23°W 2 ft. with an old  
location poster facing it. The position of the pipe conforms reasonably to the original record  
measurements to corners north, east, and west and I accept same as the best available evidence of  
the position of the original corner.

(15-Sec. 1) Established the position for the corner midway and on the Section line between Section  
corner 1328.44' west and 1328.44' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Set 1"IDx32" I.pipe with 2" alum. MDNR cap at  
the position of a found 3/4" ID pinched pipe.  
Set measuring nail with MDNR tag in the side of:  
13" Hemlock N25°E 16.7' mrkd "S1 NBT"  
10" Hemlock S58°E 44.2' "S12 NBT"  
12" Cedar N89°W 20.95' "S2 NBT"  
10" Cedar N23°W 1.85' "S2 NBT"  
Set sq'd spruce post adjacent.  
E= 7909024.948 N= 229001.073

(15) Set 1"IDx32" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
18" Hemlock N07°E 26.8' mrkd "1/16S BT"  
4" Sugar S66°E 29.15' do  
18" Y.Birch S22°W 8.5' do  
18" Hemlock N76°W 21.45' do  
Set sq'd cedar post adjacent.  
E= 7909429.766 N= 228994.455

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

