

# SURVEY & REMONUMENTATION

MAY 05 1997

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 51N R 33W

H-9

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9; One-quarter Corner common to Sections 22 and 27, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9; One-quarter Corner common to Sections 22 and 27, T51N, R33W;

Found a 1"(I.D.) x 36" galvanized iron pipe with a 4" aluminum Department of Conservation cap loosely set in 12 inches of water and in reasonable agreement with the recovered new bearing trees of record. Replaced this monument with a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap firmly set. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9; One-quarter Corner common to Sections 22 and 27, T51N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location.

i) Set 7" spike	E/side	9" Cedar	N18°E	9.24'
ii) Set 7" spike	W/side	9" Tamarack	N45°E	22.40'
iii) Set 7" spike	N/side	10" Tamarack	S82°E	22.44'
iv) Set 7" spike	E/side	10" Tamarack	S13°W	15.51'
v) Set 7" spike	SE/side	6" Tamarack	S57°W	13.86'
		Location Post	North	1.0'

(i) and (iii) are Buckler new bearing trees and are further described in Part A.

(ii) is marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(iv) and (v) are Crampton new bearing trees and are further described in Part A.

RECEIVED FOR RECORD THIS 13TH  
DAY OF NOVEMBER, 1996 AT 10:30  
A.M. AND RECORDED IN LIBER 4  
OF LAND CORNER RECORDATION  
RECORDS ON PAGES 688-689.

Richard M. Antypa  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

10-30-96

Signed by

Surveyor's Michigan License No. 39091

Date

5 Nov 1996

LIBER 4 PAGE 688



A. Description of original monument and accessories and/or subsequent restoration:

H-9; One-quarter Corner common to Sections 22 and 27, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a spruce post witnessed by a

Spruce            6            N09°W            6 lks.

and a

Spruce            6            N60°E            15 lks.

This corner is shown on sheet 14 of Michigan State Highway Department Plans, File No. S-15-A-3A, dated 1939, as being monumented by a "cedar stake". No accessories are noted.

According to a Michigan Department of Conservation Land Corner Record filed by Billy Buckler, RLS #8887 dated 4 August 1964 and recorded in Liber 2 page 340, this "corner was replaced at old Wood Post Scribed ¼. Post set by unknown Surveyor.". Mr. Buckler set a "1 (in.) Pipe with 4" Aluminum Cap" and noted the following new bearing trees:

9" Tamarack            S85°E            34 lks. (22.44')  
Presently alive and 10" in diameter having a completely healed lower blaze. Set a 7" spike on the N/side.  
Measured            S82°E            22.44'

8" Cedar            N18°E            14 lks. (9.24')  
Presently alive and 9" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the E/side.  
Measured            N18°E            9.24'

To each of the above Buckler new bearing trees I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.

Mr. Buckler's monument was recovered by Robert Crampton, P.S. #24591 on 20 October 1983. The following accessories are from a Land Corner Recordation Certificate filed by Mr. Crampton and recorded 9 December 1984 in Liber 4 page 62:

10" Cedar            N16°E            9.41'  
This is a Buckler NBT.

8" Tamarack            S82°E            22.55'  
This is a Buckler NBT.

8" Tamarack            S15°W            15.16'  
Presently alive and 10" in diameter having a partially healed mid-trunk blaze and a partially healed lower blaze in poor condition. I added an upper blaze and scribed the mid-trunk blaze "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red. Set a 7" spike on the E/side.  
Measured            S13°W            15.51'

6" Tamarack            S70°W            13.47'  
Presently alive and 6" in diameter. I added an upper and lower blaze. The lower blaze I scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red. Set a 7" spike on the SE/side.  
Measured            S57°W            13.86'

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, Mr. Buckler's monument was recovered and accepted. The BLM did not remonument the corner nor did they note any new accessories.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION