

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 33 T 51N R 34W	9
	S 28 T 51N R 34W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/05/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 33) East 1/16 corner, Section 33. Not previously monumented.

(14-Sec. 28) South 1/16 corner between Sections 27 and 28. 1978 - Established by K.L.Sackett RLS midway and on line between Section corner to south and Quarter corner to north. Set 1"ID x36" I.pipe with 4" alum. cap in back slope of highway 45 ft. north of Center Line. 9" Sugar N07°E 26.3', 12" Y.Birch N50°W 31.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 33) Established the position for the corner midway and on a straight line between Center of Section 33 1307.29' west and Quarter corner 1307.29' east.

(14-Sec. 28) Found the 1978 monument in good condition, with the NW'ly portion of the cap cracked off, at record bearing and distance from the two 1978 witnesses. The Sugar NE is in good condition with overgrown blazes. The Y.Birch is dead and down. The monument was found to be substantially at the record position and I accept same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
8" Cedar S82°E 12.85' mrkd "1/16S BT"  
4" B.Ash S14°W 6.8' do  
5" B.Ash N57°W 9.35' do  
8" Cedar N22°W 13.35' do  
Set sq'd cedar post adjacent.  
E= 7876225.483 N= 222330.247

(14) Found 1"ID I.pipe with cracked 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
11" Sugar N10°E 26.2' old blazes (1978 BT)  
7" Cedar North 24.7' mrkd "1/16S BT"  
5" Oak N38°W 12.0' do  
8" Spruce N19°W 10.1' do  
Set sq'd cedar post adjacent.  
E= 7876587.023 N= 223554.193

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID RL0593: N= 221669.506 m. E= 7868965.488 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/01/2013

For the Michigan Department of Natural Resources, Forest Resources Division

