

SURVEY &
REMONUMENTATION.

APR 26 1995

COMMISSION

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 11 PM '94

Sandy Schondelmayer
REGISTER OF DEEDS

002248

Register of Deeds Stamp & File Number

For corners in

Barry County
(County)

Located In: Yankee Springs Twp. Corner Code # D-7

1. Public Land Survey	T	3N	R	10W	D-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker, in a field survey on October 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-7, G.L.O. survey, 1830-1831, Sylvester Sibley, D.S.
A. Maple 6 N 63° W 31
A. Pine 40 N 41° E 23

LCRC #208, 1977, Williams & Works, 1" Iron
Spk E. side 14" Maple S 2.22'
Spk W. side 16" Oak E 54.78'
Spk 6" Maple N 28.07'
Spk W. side 12" Maple S 15° W 50.50'

No road Comm. info.
Co. Surveyor, 1904, Heath
Set ¼ post by stumps of original wit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7, Found 1" Iron by wit. listed in "A" above for LCRC #208 in old E-W fence and tree line.

Accepted as the best available evidence of the position of the original corner.


ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

OCT 4, 1994 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7, Replaced with 36" standard capped Barry County monument.

N & T on S. side 16" Maple West 2.53'
N & T on S. side 10" Maple East 5.33'
N & T on E. side 16" Maple Az. 200° 50.77'
N & T on E. side 10" Maple Az. 5° 72.66'
C/L E-W gravel trail is 10'± South



Robert J. Jonker
Signed by

JONKER LAND SURVEYS, P.C. 21572
Surveyor's Michigan License No.

Date December 07, 1994