

APPROVED
Date 4-20-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Calhoun	Located In:	Corner Code <u>H-11</u>
(County)		
1. Public Land Survey	T <u>3S</u> R <u>8W</u>	<u>H-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 APR 94 12:18 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Lot No. , Recorded Plat
2. Private Claims

Donald J. Davis, in a field survey on April 16, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

Resurvey by Hodgeman in 1884.	1947
Found original corner, set tile.	Tile with iron beside.
6" Hickory S 49° W 54 Links	6" Hickory East 24'
2" Maple N 40°W 53 Links	7" Oak S 65°E 34.8'
	14" Maple N 30° W 34'
	6" iron post West 30.3'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod and checked to 1947 witnesses used in local surveys.
Accepted as a true perpetuation of original corner.

SURVEY &
REMONUMENTATION


NOV 07 1994

COMMISSION

LIBER 1743 PAGE 584

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Bernstein monument in monument box in southbound lane.
Nail & Spotter in utility pole N 80° W 22.70'
Nail & Spotter in utility pole N 80° E 29.50'
Nail & Spotter in 30" Maple N 25° W 92.90'
Nail & Spotter in 24" Oak S 40° E 44.35'
6" iron post West 30.3'



signed by Donald J. Davis

Date April 19, 1994

Surveyor's Michigan License No. 17617