

APPROVED

Date Dec. 6 1995

CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
CLARENDON TWP.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

12 DEC 95 11:01 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1835 PAGE 423

Register of Deeds Stamp & File Number

Calhoun (County)
Clarendon Twp.
1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Located In: T 4 S R 5 S
Corner Code H-11

Frederick J.

I, Cutcher, in a field survey on November 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, December, 1825: Set quarter post at average distance: Tamarac 8" N. 49° E., 9 lks; Tamarack 5" S. 49° E., 8 lks.

No other records of this corner since GLO.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Traversed between Southwest corner of Section 27 and Southeast corner of Section 27. Determined South 1/4 post of Section 27 to be 1/2 way by single proportionate method. No corner set due to drainage ditches running North, South, East & West.

COMMISSION
REMONUMENTATION


FEB 2 2 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

No physical corner set. This position is accepted as a careful and faithful reestablishment of the position of the original corner.

1/2"x18" iron rod at N.W. corner Ditch Bank N. 31° 19' 13" E., 43.30'.
S.W. cor. Sec. 27 N. 89° 21' 04" W., 2657.87'.
S.E. cor. Sec. 27 S. 89° 21' 04" E., 2657.87'.
N. 1/4 post Sec. 27 N. 00° 04' 34" E., 5308.84'.



Signed by Frederick J. Cutcher
Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date December 5, 1995