

MAY 28 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner

For corners in

Chippewa County Located in: Corner Code # 1. Public Land Survey **T46N R1F** F-9 Т R τ R 2. Property Controlling S T R in Section S T R 3. Miscellaneous S Τ R Property in Sec. S

\$7.00 LAND CORNER

\$2.00 MSSR

10

2/28/1997 3:10:09 PM Receipt #217 RECEIVED FOR RECORD

EHIPPENA COUNTY - ETATE OF MICHIGAN SHARON H. KENNEDY, REDISTER OF DEED

ROOK 9 PAGE 372

Register of Deeds Stamp & File Number


Lot No.

, Recorded Plat

5. Private Claims

I, William L. Karr, in a field survey on August 28, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



(E-9) Section Corner Common to Sections 20,21,28 & 29, T. 46 N., R. 1 E.

J.H. Mullett set post in Original Survey.

1902 F.H. Brown in records in County Surveyors Office found post set by Carleton for section corner.

Corner Tie Book in County Surveyors Office shows monument and cedar post for corner and ties to fence

1984 W.L. Karr, PS 27450, found no evidence of original corner. Found 3/4" iron 8" below surface in road intersection and accepted for corner. Recorded Liber 6, Page 132, Chippewa County Corner Records.

L.R. Rogers, PS 29251, in a survey in section 21, Northwoods Land Surveying job number 141-37, found 3/4" iron as recorded by Karr 3.5' below surface and raised with a 1/2 x 48" re-bar with cap number 29251.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-9) Section Corner Common to Sections 20,21,28 & 29, T. 46 N., R. 1 E. This comer is being perpetuated as part of the Chippewa County Remonumentation Program.

Found corner as recorded by Karr in 1984 and raised to surface by Rogers in 1992. Accepted corner position as found.

WONUMEN TO THE PROPERTY OF THE WINDS OF THE PROPERTY OF THE P C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-9) Section Corner Common to Sections 20,21,28 & 29, T. 46 N., R. 1 E.

Corner is a 1/2" x 48" re-bar with plastic cap no. 29251 in road intersection, 4.6' west of centerline of North and South road and 4.4' north of centerline road to West. Corner is 0.5' below grade.

Witnesses:

6" Oak S 75° E 111.29 Power Pole S 30° E 64.73 Power Pole S 36° W 61.77 (DR1/76/15) Fence Post N 35° W 44.96

MI KARR LAND SURVEYOR No. 27450

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the otherwise noted.

Surveyor's Michigan License No. 27450

Date 12-30-96