

MAY 28 1997

COMB STA

## LAND CORNER RECORDATION CERTIFICATE . 00 LAND CORNER

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner 2/28/1997 3:03:43 PM

For corners in

Chippewa County Located in: Corner Code # 1. Public Land Survey **T46N** R1E H-11 T T R 1 R 2. Property Controlling T R in Section S T 3. Miscellaneous S R Property in Sec.

RECEIVED FOR RECORD IHIPPENA COUNTY - STATE OF MICHIGAN

Receipt #21%

BANKON H. KEINASIA REGISTER OF DEEL

800K 9 PAGE 364

D

3

у

9

Register of Deeds Stamp & File Number


4. Lot No.

, Recorded Plat

5. Private Claims

I, William L. Karr, in a field survey on November 13, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



## (H-11) 1/4 Corner Common to Sections 27 & 34, T. 46 N., R. 1 E.

1845 J.H. Mullett used a 6" black ash for section corner.

- 19?? F.H. Brown in records in County Surveyors Office for a survey in section 34. Notes show the old corner gone and the mile evenly divided.
- 1983 W.L. Karr, PS 27450, found no evidence of Brown's survey and reestablished the corner on line with North and South 1/4 line fences, and midway between right-of-way fences on the North and South sides of the road line fences. set a 1" x 36" drill rod and recorded the corner in Liber 6, Page 120, Chippewa County Corner Records
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

## (H-11) 1/4 Corner Common to Sections 27 & 34, T. 46 N., R. 1 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found the drill rod as recorded by Karr in 1983, 8' South of centerline East-West gravel road and 2' below graveling military.

Accepted corner as found and raised to the surface with a 3/4" re-bar and cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

## (H-11) 1/4 Corner Common to Sections 27 & 34, T. 46 N., R. 1 E.

Corner is a 3/4" x 24" re-bar with plastic Chippewa County Remonumentation Cap, 8' South of centerline 1 Corner is 0.5' below grade.

Witnesses:

24" Elm N 79° E 235.81 Section Corner 2603,28 East Witness Pipe S 45° E 60.97 Witness Pipe S 45° W 60.42 Section Corner West 2610.37

Bearings are compass bearings, corrected for declination, distance to Elm is to a nail and tag in the side of the are 3/4" x 24" pipes with pipe caps set 1' below the surface. No other acceptable witnesses available.

Signed by \_

Date 12-30-96

Surveyor's Michigan License No. 27450

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 REVISED OCT., 1995

KARR

LAND

**SURVEYOR** 

No.