

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:15

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File No.

1. Public Land Survey

| | | | | | |
|---|-----|---|----|------|----------------|
| T | 45N | R | 1E | K-1 | Same Corner |
| T | 46N | R | 1E | K-13 | |
| T | | R | | | |
| T | | R | | | |
| T | | R | | | |

2. Property Controlling
in Section

| | | | | | |
|---|--|---|--|---|--|
| S | | T | | R | |
| S | | T | | R | |
| S | | T | | R | |
| S | | T | | R | |

3. Miscellaneous
Property in Sec.

| | | | | | |
|---|--|---|--|---|--|
| S | | T | | R | |
| S | | T | | R | |
| S | | T | | R | |
| S | | T | | R | |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I |
|----|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | |
| 3 | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | |
| 5 | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | |
| 7 | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | |
| 9 | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | |
| 11 | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | |
| 13 | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(K-1) Northeast Corner of Section 2 (T45N-R1E)

Original ties: 10" Cedar N32°W 10 links 10" B. Ash N40°E 9 Links

1990: Keith Waters found and accepted a 1½" pipe (Liber 7, Page 220).

| | | |
|--------------------------|-------|--------|
| Power Pole (DR1-76E-24M) | S56°E | 32.31' |
| 24" White Pine | East | 34.57' |
| 6" Balsam Fir | N34°W | 65.13' |
| Street Sign | S42°W | 43.95' |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-1) Found corner and all accessories as recorded in Liber 7, Page 220 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

DEC 18 1995

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-1) Corner is a 1½" iron pipe.

| | | | |
|------------|--------------------------|-------|--------|
| Witnesses: | Power Pole (DR1-76E-24M) | S56°E | 32.31' |
| | 24" White Pine | East | 34.57' |
| | 6" Balsam Fir | N34°W | 65.13' |
| | Street Sign | S42°W | 43.95' |

Signed by _____

Date

20 JULY 1994

Surveyor's Michigan License No. 29251

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN.
REVISED MAY
REVISED JA

LIBER 8 PAGE 329