

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

2. Property Controlling  
in Section

S\_\_\_ T\_\_\_ R\_\_\_  
S<sub>4</sub> T<sub>49N</sub> R<sub>7W</sub> 10  
S<sub>4</sub> T<sub>49N</sub> R<sub>7W</sub> 3

3. Miscellaneous  
Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

3 Oct 26 2005  
10 Oct 03 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 4) South 1/16 corner between Sections 4 and 5. Not established in the original survey. Found no subsequent record.  
(3-Sec. 4) North 1/16 corner between Sections 4 and 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 4) Found a 1" ID iron pipe, set by an unknown surveyor, said pipe being located 0.60' West and 0.14' South of a position midway and on line between Section corner E3 and Quarter corner E2. Accepted same as a careful and faithful determination of the position of the corner. Left the pipe in place and drove an aluminum MDNR cap into it.  
(3-Sec. 4) Established the corner on the Section line between corners E1 and E2 and 20 chains, proportionate to the original record, north of E2. The position is thus 1346.67' north of E2 (20.00 ch R) and 1323.78' south of E1 (19.66 ch R).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Fd 1" ID I.pipe. Set 4" alum. MDNR cap in top. Set measuring nails in:  
4" Balsam N86E 17.17' mrkd "S1/16 BT"  
10" J.Pine S06E 33.1' do  
12" J.Pine N70W 13.22' do  
10" J.Pine N07E 57.7' do  
Bearings are magnetic. Distances are to nail with tag. A NW-SE trail road is 40' North.  
(3) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
9" Cedar N81E 47.0' mrkd "N1/16 BT"  
5" W.Birch N56E 27.7' do  
12" W.Birch N12W 39.25' do  
14" Cedar N30W 55.5' do  
Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski

Date 2/21/06

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities