
## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

Crawford (County)	Located In	Corner Code #	
<ol> <li>Public Land Survey</li> <li>Property Controlling in Section</li> <li>Miscellaneous Property in Section</li> </ol>	T     28N     R     3W       T     28N     R     3W         S     T     R       S     T     R       S     T     R       S     T     R	E-7 E-8	Register of Deeds Stamp & File Number
4. Lot No: 5. Private Claims:	Recorded Plat:		A B C D E F G H I J K L M
requirements of PA 74, Mi and 2 above were in confo the current manual of sur Interior, Bureau of Land Ma corner points mentioned in of the Michigan Board of	d survey on August 11, 2008 do here chigan PA of 1970, the corner points numance with regulations and rules there vey instructions of the United States anagement or by a decree of a Court of lines 3, 4 and 5 above were in conform of Land Surveyors or by a Decree of a manumented recovered found as expressions.	mentioned in lines 1 refore as required in Department of the Law and/or that the mance with the rules of a Court of Law;	3

A. Description of original monument and accessories and/or subsequent restoration:

NOTE: Not more than 2 corners, all in the same town and range, may



Wit: Beech 8 N51°E 21 links Beech 8 \$58°30'E 25 links

1970 Kenneth J. Ostling R.L.S. #10068 found a RR iron of long standing acceptance at corner.

Wit: Maple 32" N55°W Maple 23" S81°W 51.0' 54.9

be recorded on this certificate.

Wit: Birch 15 S15°E 20 links Elm 18 N56°W 17 links

10

1970 Kenneth J. Ostling R.L.S. #10068 set corner by proportionate measurement with the U.S. record deflection.

Wit: Tw. R. Pine 8" S70°W 37 8 Tw. R. Pine 12" S41°W 62.5'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

E-7 Found ½" iron in a monument box fitting K.J. Ostling's survey in section 20.

E-8 Found ½" iron rod fitting one of K.J. Ostling's witnesses and his survey in section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Found 1/2" Iron

Wit: Found nail and tag #43046 in South side of a 40" Maple S85°W 56.03'

Set nail and tag in Southwest side of a 18" Maple N43°W 53.55' Set nail and tag in South side of a 6" White Pine N44°E 52.13' Set nail and tag in Southeast side of a 10" Maple S12°E 82.77'

E-8 Set 1" X 48" iron pipe with P.S. cap #33981 Wit: Set nail and tag in North side of a 7" White Pine N73°E 54.65' Set nail and tag in North side of a 10" Jack Pine S72°E 58.70' Set nail and tag in North side of a 12" twin Red Pine S75°W 38.38' Set nail and tag in Northeast side of a 6" Cherry N54°W 76.79' Set Carsonite Post West 33'±

Signed by: Surveyor's Michigan License No.:

Date:

CARL KIISKILA LAND SURVEYOR GENSED LAND SUR 33981