

APR 07 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford

(County)

Located in:

Corner Code #

1. Public Land Survey

T 26N R 2W

A-1

T 27N R 2W

A-13

T 27N R 3W

M-13

T 26N R 3W

A-13

2. Property Controlling  
in Section

S T R  
S T R

3. Miscellaneous  
Property in Sec.

S T R  
S T R

4. Lot No. , Recorded Plat

5. Private Claims

LIBER

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

19 DEC 97 2:36 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File  
Number

3 PAGE 281

I, Marvin E. Myers, in a field survey on 27 MAY, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
15 June 1852  
Darwin A. Pettibone D.S.  
Mon: Post  
Wit: 24" Pine S71°W 1.00 links  
18" Yellow Pine N80°E 1.29' links  
12" White Pine N18°W 0.94 links

1955 George D. Henning R.L.S.  
Unrecorded Survey Sec.6 T26N R2W  
Restored from stumps of original U.S.  
witnesses  
Mon: 3/4" square bar in blacktop 9' N.  
of centerline  
Wit: 4" Jack Pine N58°W 58.1  
8" Jack Pine N41°E 37.00'  
7" Jack Pine S31°W 62.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert T. Ostling R.L.S.#5133  
Liber 1 Page 59, 14 August 1959  
Plat of Ausable Trails  
Mon: 3/4" iron in pavement  
Wit: none provided

Eugene Ostling R.L.S.#12026  
Unrecorded survey, 4 Sept 1971  
Mon: 3/4" square iron  
Wit: none provided

Norman F. Parker R.L.S.#16939  
Liber 148 Page 07, 26 Sept 1975  
Mon: no description provided  
Wit: none provided

Norman F. Parker R.L.S.#12026  
Unrecorded survey 29 Dec 1986  
Mon: no description provided  
Wit: none provided


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found Rail Road spike flush with the asphalt surface 8.5' north of centerline. Verified position by measurement to corners East and West. Accepted position as a perpetuation of the original government Corner, replaced railroad spike in exact location with standard County Monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Mon - Standard Crawford County monument in Pavement Monument box.

Wit: Spike in Southeast side Utility Pole S63°W 60.60'  
Set spike in West side 13" Red Pine S36°W 76.90'  
Set spike in East side 8" White Pine S38°E 87.60'  
Set spike in 8" Jack Pine N20°W 43.63'

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE 007 16, 1997

Marvin E. Myers  
Marvin E. Myers, P.S.  
County Surveyor



Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date Dec 15, 1997