

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>33</u> N. <u>0.</u> R. <u>4</u> W. <u>0.</u>	<u>B-13;</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 19, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
B-13 - Restored S $\frac{1}{4}$ corner Sec. 31 (T33N-R4W), N $\frac{1}{4}$ corner Sec. 6 (T32N-R4W), per E.A. Robinson survey of N. line of Sec. 6, dated May 14, 1906; see Hudson (32-4), Bk. C-296, pg. 10, at Jury Room in courthouse. Robinson's notes say "at 21.25 ch. W. of 1/4 Corner - small spring, rivulet that soaks into ground on his random between fd. 1/4 Corner from Govt. B.T.'s (spring was on line extended W. bet. NE & N $\frac{1}{4}$ Cor. of Sec. 6 (32-4). We recovered this spring, very definate, to restore $\frac{1}{4}$ Cor. & prorated to E.A. Robinson bet. fd. NE & NW of Sec. 6. Fits his var. of the compass reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13
Set DNR monument & cedar post
5" Maple N20°E 15.1'
6" Maple S88°E 35.5'
6" Ironwood S48°E 25.1'
4" Maple N60°W 38.5'
Fd. 2" Schaaf pipe
(drove flush) N67°11'E 89.3'

SIGNED BY Carl F. Roser 02-07-86 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHARLEVOIX COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET