

SURVEY & REMONUMENTATION

1997 CHEBOYGAN COUNTY, STATE OF MICHIGAN REMONUMENTATION

FEB 26 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

CHEBOYGAN
(County)

Located In:

Corner Code #

1. Public Land Survey

T 35 R 3W K-6
T R
T R
T R
S T R
S T R
S T R
S T R

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Ronald Bischer, in a field survey on Oct 2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6
GLO notes
Harvey Mellen
1855 Resurvey
Set Post
20" White pine N82° E 27 lks
20" White Pine N09° W 11 lks

1953 Orlando Doyle #7319
Found 1" pipe and set 3 witnesses
1962 Dean DelaMater #5778
found Con. Mon and set 2 witnesses
1982 Ronald Bischer #22428
Found Conc. Mon. and Cap #10710
1990 James Granger #16041
Found Conc. Mon. & Cap #10710
set four witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-6
Found Conc. Mon. and Cap #10710
found both DelaMater witnesses
found Two Bischer and Granger witnesses
Set Monument box on corner and set Remon cap
atop concrete monument

LIBER 011 PAGE 58

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6
Remon cap on Concrete Monument in Monument box

N89° W 26.43' 18" Red Oak
S32° W 52.01' 19" White Oak
N32° W 50.30' 19" White Oak
N60° W 26.09' 12" White Pine

DelaMater witness
DelaMater witness
Bischer witness
Granger witness



12-22-97
RECEIVED FOR RECORD
at 9:10 O'Clock A M

Joanne Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |



Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Oct. 10, 1997