

JAN 23 1996

COMMISSION

CHEBOYGAN COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CHEBOYGAN

(County)

Located In:

Corner Code #

1. Public Land Survey

T 35N R 3W

M-8

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED
FOR RECORD

95 DEC 26 PM 2:36

James Spray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, RICHARD C. DUNN, in a field survey on AUGUST, 19 95,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:



G.L.O. John Mullett 1840
Set 1/4 Sec. Post
No Witnesses

Orlando Doyle #7319, Feb. 1948
Fnd. 1" Iron
24" Balm of Gilead NW 61.75'
8" Tamarack NE 61.02'
P.Pole SE 59.24'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron 2.9' North of Road Centerline. Checked with monuments during recent survey in nearby Indian
Riverside Resort Subdivision in Liber 3, page 12 of Plats, Cheboygan County Records.

Martin D. P...



C. Description of monument for corner and accessories established to perpetuate location of the position of the corner:

M-8 Found 1" Iron and is accepted as a careful and faithful reestablishment of the position of the original corner.
Re-placed w/5/8" re-rod and remonumentation cap in Monument Box.
Light Pole w/tag 15410 S7°W 23.75'
P.Pole w/nail N34°E 103.44'
SE Cor. Garage N18°W 92.43'
10" Aspen, Set PK S52°W 46.88'
C/L Onaway Road South 2.9'
C/L Wood Street East 21.6'

LIBER 010 PAGE 140

Signed by

Richard C. Dunn

Date DECEMBER 4, 1995

Surveyor's Michigan License No. 12020