

SURVEY & REMONUMENTATION

1993

COMMISSION

CHEBOYGAN COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHEBOYGAN
(County)

Located In:

Corner Code #

1. Public Land Survey T 37N R 1E A-2
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED
FOR RECORD

93 DEC 22 AM 10:56

James L. Gray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Ronald R. Bischer, in a field survey on September 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

A-2
Original Survey - June 1840
John Hodgson set Wood Post
6" Pine S44°E 13 links
6" Pine N63°W 10 links
1963 - Kenneth Ostling
set ½" Rod by proportionate
measurement between section
corners
7" R. Pine N28°E 18.5'
10" R. Oak S29°W 90.9'
1964 - Kenneth Larsen
½" Rod - same witnesses
as above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2
Found ½" Rod in gravel road
Road has been widened, all old witnesses
have been cleared away.
½" Rod agrees with single proportion
measurement made on September 23, 1993.
Replaced ½" Rod with Cheboygan County Remonumentation Monument.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													




LIBER 010 PAGE 28

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2
Cheboygan County Remonumentation Monument
S29°E 41.16' 4" Red Oak
S33°W 80.87' 8" Jack Pine
S87°W 41.35' 12" Red Pine
N29°W 74.34' 6" Red Pine

Set nail with witness tag #22428 in witnesses.

Marilyn A. Perry



Signed by Ronald R. Bischer

Date 12-03-93

Surveyor's Michigan License No. 22428