

MAR 22 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

CHEBOYGAN

(County)

Located In:

Corner Code #

1. Public Land Survey

T 38NR 2W

1-7

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

I, JAMES H. GRANGER, in a field survey on JULY 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Original Survey Set wood post 14" Cedar S64°E 20 lks  
Harvey Mellen 16" Cedar S11°W 7 lks

1913 County Surveyor Found 4" x 4" cedar post  
George Annud

1951 Survey Found cedar stake  
Orlando Doyle #7319

1953 Survey 3/4" pipe  
Orlando Doyle #7319

1988 Survey 1" pipe  
James H. Granger #16041

1998 Survey Found 1" pipe  
David Grondin

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe and 4 existing overgrown witnesses, with 3 new witnesses set over them in existing witness trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" rebar and remonumentation cap inside 1" pipe  
6" Fir S87°W 5.97' Fd tag  
8" Fir N49°W 11.14' Fd tag  
12" Poplar N43°E 21.33' Fd nail and washer  
8" Poplar S46°E 11.72' Fd tag



RECEIVED FOR RECORD 12-7-98  
at 9:24 O'Clock A. M

Joanne Spray

CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

| 1  | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |



Signed by James H. Granger  
License No. 16041

Date November 2, 1998 Surveyor's Michigan