

MAR 22 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

CHEBOYGAN
(County)

Located In:

Corner Code #

1. Public Land Survey

T___ R___
T___ R___
T___ R___
T___ R___

2. Property Controlling
in Section

S 31 T 39NR 2W
S 6 T 38NR 2W

3. Miscellaneous
Property in Sec.

S___ T___ R___
S___ T___ R___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, JAMES H. GRANGER, in a field survey on JULY 15, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 Original Survey
John Mullett

Set wood post

8" Cedar
8" Spruce

S33°E
S71°W

51 lks
63 lks


RECEIVED FOR RECORD 12-7-98
at 9:07 O'Clock A. M

Joanne Gray

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found. Established witness position on North Section line extended East parallel to South Section line.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" rebar and Remonumentation Cap
14" Cedar S56°E 26.75' Set tag #16041
10" Spruce S26°E 16.04' Set tag #16041
14" Spruce S46°W 34.84' Set tag #16041
16" Spruce N70°W 23.53' Set tag #16041
Original Meander Corner 34.6 ft. on Township line extension

Signed by James H. Granger
License No. 16041

Date November 2, 1998 Surveyor's Michigan