

# SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

( ) DELTA County Code No.

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 12/27, 1996  
*Hubb Schmelting*  
acting Chairman

For corners in

DELTA  
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 38 N R 23 W

MC F/G-7 WEST BANK

T 38 N R 23 W

MC F/G-7 EAST BANK

T R

(19)

T R

Other #19

2. Property Controlling

S T R

in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

Recorded Jan 2 1997

at 3:00 o'clock PM

Liber 8 Page 200

*Walter C. Thorne*

Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

F/G-7 [MC S/L BETW 16/21 WEST BANK OF FORD RIVER]

F/G-7 [MC S/L BETW 16/21 EAST BANK OF FORD RIVER]

I, M.P. DAVIS, in a field survey on MAY/MARCH, 19 96,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F/G-7 [MC WEST BANK] WOOD POST - A.MERRYWEATHER, D.S. - 1847 (BALSAM 10°-N50°W-12 LINKS) (CEDAR 05°-S15°W-09 LINKS)  
NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT MONUMENTATION.

F/G-7 [MC EAST BANK] WOOD POST-A.MERRYWEATHER, D.S. - 1847 NO WIT'S NOTED  
NO RECORD EVIDENCE OF CORNER RECOVERY OR SUBSEQUENT MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F/G-7 [MC WEST BANK] NO CORNER EVIDENCE FOUND. ESTABLISHED CORNER POSITION ON A STRAIGHT LINE WITH THE SEC COR TO THE EAST & THE 1/4 COR TO THE WEST AND PROPORTIONATE DISTANCE BETWEEN THEM. IT APPEARS THAT THERE HAS BEEN DRAMATIC CHANGES IN THE FORD RIVER, WHETHER MANMADE OR NATURAL IS UNKNOWN AS THE WIDTE OF THE PRESENT RIVER IS SOME 140' NARROWER THAN SHOWN IN THE ORIGINAL SURVEY AND THE CORNER POSITION IS 150 M/L WEST OF THE PRESENT WEST BANK OF THE FORD RIVER.

F/G-7 [MC EAST BANK] NO CORNER EVIDENCE FOUND AS CORNER POSITION NOW FALLS IN THE FORD RIVER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F/G-7 [WEST BANK] SET A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
CEDAR 08" ASH 11" SURVEY MONUMENT SIGN POST  
N47°W S59°W NORTH  
79.12' 20.38' 2.28' (TO FACE)

F/G-7 [EAST BANK] CORNER POSITION FALLS IN FORD RIVER NO MONUMENT SET.  
REFERENCE MONUMENT - CORNER COMMON TO SEC'S 15,16,21 & 22 AS MONUMENTED 1 CHAIN TO THE EAST

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis Date 12/26/96

Surveyor's Michigan License No. 16926

