

JAN 22 2000

SECTION

For corners in
DELTA
(County)

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On December 30, 1998
Robert R. Schmelzing
Chairman

	Located In:	Corner Code #
1. Public Land Survey	T 40 N R 19 W	MC F/G-9 (15)
	T 40 N R 19 W	MC G/H-1 (23) ✓
	T 41 N R 19 W	MC G/H-13 (5)
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED Jan 11 1999
9:45 AM
9 Page 133
William C. Thomas
Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
F/G-9 [M.C. SEC 21/28] G/H-1 & G/H-13 SAME COR [M.C. N. LINE SEC 3 T40N R19W
S. LINE SEC 35 T41N R19W]

I, M.P. DAVIS, in a field survey on DECEMBER, 19 98,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F/G-9 [MC SEC. 21/28] A. MERRYWEATHER D.S. - 1848 - WOOD POST (SOFT MAPLE 08"-N15°W-97 LINKS)
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR MONUMENTATION.
G/H-1 [MC N. LINE SEC 3] JOHN BURT, D.S. - 1845 - CEDAR 16" CORNER TREE
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F/G-9 [MC SEC 21/28] FOUND IN PLACE AT NEARLY THE "GLO" DISTANCE EAST OF THE 1/4 CORNER COMMON
TO SECTIONS 21/28 A 5/8" IRON PIN. NO OTHER WIT'S OR ACCESSORIES OBSERVED. ACCEPTED
EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE ORIGINAL
CORNER POSITION.

G/H-1 [MC N. LINE SEC 3] NO CORNER EVIDENCE FOUND. RESTORED CORNER POSITION ON THE 4TH CORRECTION
LINE NORTH AND BEING ON LINE WITH THE SE COR OF SEC 35 T41N R19W AND THE 1996 B.L.M. MEANDER
CORNER ON THE WEST SIDE OF MOSS LAKE. AS THE DISTANCE BETWEEN THESE TWO CONTROL POINTS MEASURES
5.5 CHAINS LONGER THAN THE "GLO" DISTANCE AND AS THE "GLO" DISTANCE FROM THE SE COR OF SEC 35
TO THE PRESENT EAST SHORE OF MOSS LAKE MATCHES WITH THE GIVEN "GLO" DISTANCE IT WAS DECIDED TO
SET THE M.C. AT THE "GLO" DISTANCE AND NOT ATTEMPT TO PROPORTION OUT THE LARGE ERROR FOUND TO
EXIST IN THE RECORD DISTANCE CROSSING MOSS LAKE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F/G-9 SET, OVER EXISTING MONUMENT, A BERNTSEN AINB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
ASH 04" CEDAR 04" MAPLE 16" SURVEY MONUMENT SIGN POST
N85°E S10°W S85°W EAST
62.68' 6.06' 48.87' 2.10' (TO FACE)

G/H-1 SET BERNTSEN AINB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 08" CEDAR 13" ELM 06" SURVEY MONUMENT SIGN POST
N11°E S27°E N77°E WEST
46.48' 44.98' 20.21' 0.89' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/28/98

Surveyor's Michigan License No. 16926

