

FEB 2 2 1996

For corners in

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
2 A Of 1000 On Auto 13 100 A

P.A. Of 1990 On July 13, 199 4

Mark Johnsling

acting Chairman

_	DELTA (County)	Located In:	Corner Code ##	
1.	Public Land Survey	T 39 N R 24 W T R R 24W	I-1 & I-2 I-/3	Recorded Aug 12 1994 st 9:00 clock AM in Liber 8 Page 42
2.	Property Controlling in Section	TR \$ T R S		Organ County, Michigan
3.	Miscellaneous Property in Sec.	S T R S T R		Register of Deeds Stamp & File Number
		COR S.2] I-2 [W1/4 COR S.2]		2 6 5 4 3 - 2 1 1 3 4 7 8 8 9 9 10 11 12 12
1	M.P. DAVIS	is a field survey on	MAY	94

I, M.P. DAVIS , in a field survey on MAY , 19 94 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded

on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-1 [NW COR S.2] JANES H. MULLETT, D.S. - 1848 - WOOD POST (CEDAR 12"-N52"E-14 LINKS) (CEDAR 12"-N34"W-13 LINKS)

GEORGE ADAIR, D.S. - 1852 - WOOD POST (HEMLOCK 26"-S77"W-15 LINKS) (CEDAR 14"-S39"E 28 LINKS)

M.S.McNABB - 1934 - ID BY "STAKE IN ROAD" NO NEW WIT'S NOTED

R.P.MASON - 1937 - SQ'D STAKE IN PLACE - REFERENCES PLAIN


M.DAVIS - 1978 -RESTORED FROM LINES OF OCCUPATION & RD IMPROVEMENTS (PP-S46°W-63.7') (PP-S43'E-43.0') SET I.P W/A SURVEY CAP IN MON BOX & REC'D IN L.2 OF LCR'S ON PAGE 478.

- I-2 [WI/4 COR S.2] GEORGE ADAIR, D.S. 1852 -WOOD POST (CEDAR 16"-N50°E-08 LINKS) (Y.BIRCH 10"-S56°N-10 LINKS)

 M.DAVIS 1978 RESTORED CORNER POSITION FROM ANCIENT LINES OF OCCUPATION & COUNTY ROAD IMPROVEMENTS. SET, INSIDE A MONUMENT
 BOX A 1" I.P W/A SURVEY CAP (CEDAR 8"-N57°W-40.15') (POWER POLE-S13°E-96.8') AND REC'D IN LIBER 2 OF LCR'S PAGE 478
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

 1-1 [NW COR S.2] FOUND IN PLACE A 1" I.P. W/A SURVEY CAP SET INSIDE A MON BOX. THIS CORNER WAS
 ESTABLISHED BY MYSELF IN 1978 AND REC'D IN LIBER 2 OF LCR'S ON PAGE 478. THIS CORNER WAS RESET
 FROM THE RETRACEMENT OF MCNABB'S 1934 SURVEY OF THE LINE COMMON TO SEC'S 34/35 T40N R24W.

 THIS POSITION MATCHES WITH EXISTING LINES OF OCCUPATION & PRESENT COUNTY ROAD IMPROVEMENTS AS
 WAS FOUND TO EXIST IN 1978. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS
 TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER. ALL ACCESSORIES ESTABLISHED IN 1972
 HAVE BEEN REMOVED.





- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - I-1 REPLACED I.P. W/A 5/8' X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

GALV ROAD SIGN POST POWER POLE POWER POLE SURVEY HONUMENT SIGN POST

N34°W S44°E S47°W EAST

43.64' (TO FACE) 42.43' (TO FACE) 63.30' (TO FACE) 17.95' (TO FACE)

I-2 SET, INSIDE A MONUMENT BOX, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

 CEDAR 10"
 ELM 12"
 CEDAR 6"
 SURVEY MONUMENT SIGN POST N59°W
 N86°W
 N42°E

 39.77'
 46.16'
 43.38'
 27.04' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG IN THE OBJECT, UNLESS OTHERWISE NOTED.

NOTE: DERRINGS TO REFERENCE UDUECTS ARE PROPERTY OF	DISTANCES ARE TO A MATE W/R REFERENCE ING IN THE OBJECT, UNBESS CINERWISE NOTED.
Signed by Mitibauij	1/20/20
Signed by	Date 6/30/94
Surveyor's Michigan License No. 16926	FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971