

JAN 22 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On December 30, 1998

*Robert B. Schmidt*  
Chairman

For corners in

DELTA

(County)

Located In:

Corner Code ##

1. Public Land Survey

T 40 N R 19 W

MC F/G-9 (15)

T 40 N R 19 W

MC G/H-1 (23)

T 41 N R 19 W

MC G/H-13 (5) ✓

T R

2. Property Controlling

S T R

in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

F/G-9 [M.C. SEC 21/28] G/H-1 & G/H-13 SAME COR [M.C. N. LINE SEC 3 T40N R19W & S. LINE SEC 35 T41N R19W]

I, M.P. DAVIS, in a field survey on DECEMBER, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F/G-9 [MC SEC. 21/28] A.MERRYWEATHER D.S. - 1848 - WOOD POST (SOFT MAPLE 08"-N15°W-97 LINKS)  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR MONUMENTATION.

G/H-1 [MC N. LINE SEC 3] JOHN BURT, D.S. - 1845 - CEDAR 15" CORNER TREE  
NO RECORD EVIDENCE OF SUBSEQUENT CORNER RECOVERY AND/OR MONUMENTATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F/G-9 [MC SEC 21/28] FOUND IN PLACE AT NEARLY THE "GLO" DISTANCE EAST OF THE 1/4 CORNER COMMON TO SECTIONS 21/28 A 5/8" IRON PIN. NO OTHER WIT'S OR ACCESSORIES OBSERVED. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE ORIGINAL CORNER POSITION.

G/H-1 [MC N. LINE SEC 3] NO CORNER EVIDENCE FOUND. RESTORED CORNER POSITION ON THE 4TH CORRECTION LINE NORTH AND BEING ON LINE WITH THE SE COR OF SEC 35 T41N R19W AND THE 1996 B.L.M. MEANDER CORNER ON THE WEST SIDE OF MOSS LAKE. AS THE DISTANCE BETWEEN THESE TWO CONTROL POINTS MEASURES 5.5 CHAINS LONGER THAN THE "GLO" DISTANCE AND AS THE "GLO" DISTANCE FROM THE SE COR OF SEC 35 TO THE PRESENT EAST SHORE OF MOSS LAKE MATCHES WITH THE GIVEN "GLO" DISTANCE IT WAS DECIDED TO SET THE M.C. AT THE "GLO" DISTANCE AND NOT ATTEMPT TO PROPORTION OUT THE LARGE ERROR FOUND TO EXIST IN THE RECORD DISTANCE CROSSING MOSS LAKE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F/G-9 SET, OVER EXISTING MONUMENT, A BERNTSEN A1NB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.  
ASH 04" CEDAR 04" MAPLE 15" SURVEY MONUMENT SIGN POST  
N85°E S10°W S85°W EAST  
62.68' 6.06' 48.87' 2.10' (TO FACE)

G/H-1 SET BERNTSEN A1NB30 ALUMN MON. W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION.  
CEDAR 08" CEDAR 13" ELM 05" SURVEY MONUMENT SIGN POST  
N11°E S27°E N77°E WEST  
46.48' 44.98' 20.21' 0.89' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis

Date 12/28/98

Surveyor's Michigan License No. 16926

Register of Deeds Stamp & File Number

Jan 11 1999  
9:45 AM  
9 Page 133  
*William C. Flinn*  
Delta County Reg. of Deeds

A	B	C	D	E	F	G	H	I	J	K	L	M
6	5	4	3	2	1							
7	8	9	10	11	12							
18	17	16	15	14	13							
19	20	21	22	23	24							
30	29	28	27	26	25							
31	32	33	34	35	36							

