

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 40N R 29W

E8

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Oct 24 2000

I, Paul R. Bressette, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E08) Quarter corner common to Sections 20 and 21. 1849: James H. Mullett, DS. Set wood post witnessed by: Hemlock 12 N20E 29 lks.; W. Pine 24 N80W 13 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E08) No evidence of original survey or subsequent restoration found. Measured to feature calls from a mid-point and on-line position. Measured south 66 feet to top of a ridge (GLO-1 chain-"summit 15 feet"); measured north 100 feet to check "begin to descend" at 1.5 chains, hill falls away, but not a distinct call. Following the line further north, line hits on narrow spot where remnants of stream run close to base of hill (GLO-"stream 03 c ESE rapid and ascend"). Based on these measurements, corner position was reestablished mid-point and on-line between the Northwest and Southwest corners of Section 21, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E08) DNR monument

11" Spruce N38E 24.3' (1/4S,NBT)

06" Sugar S40E 12.1' (1/4S,NBT)

09" Maple S39W 31.0' (1/4S,NBT)

07" Sugar N49W 7.6' (1/4S,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette

Date _____

Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division