

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
Felch Township		
1. Public Land Survey	T 42N R 29W	I05
	T 42N R 29W	K02
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

I, Jeremy J. Pipp, in a field survey on 7/31/2012AD do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I05) Corner common to Sections 10, 11, 14, and 15. 1849: John Burt,DS. Set Cedar post  
witnessed by Lynn 16 S35E 26 links (17.16'), Sugar 16 N43W 28 links (18.48').

(K02) Quarter corner common to Sections 1 and 2. 1849: John Burt,DS. Cedar 16 Quarter  
Section Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I05) No evidence of original survey or subsequent restoration found. Corner position reestablished by double  
proportionate measurement between Section Corners One Mile North, Two miles East, 1/2 mile South, and One Mile  
West. Position checks well with line calls North & South ("74.00 Chains - Top of knob of ridge"), ("75.00  
Chains - Enter Swamp"), ("79.00 Chains - Leave Swamp"), ("1.50 Chains - Top of Ridge"). Position is accepted  
as a careful and faithful REESTABLISHMENT of the position of the original corner.

(K02) No evidence of original survey or subsequent restoration found. Several large Cedar stumps in vicinity  
but nothing defininate. Corner position reestablished by single proportionate measurement between the  
Southeast corner and the Northeast corner of Section 2. Position checks within reason to adjacent 'Top of  
Ledge of Marble' call North. Position is accepted as a careful and faithful REESTABLISHMENT of the position of  
the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I05) DNR monument  
9" Maple N36E 13.33' (S11,NBT)  
7" Aspen S15E 11.70' (S14,NBT)  
4" Tw. Ironwood S24W 16.10' (S15,NBT)  
10" Maple N51W 7.17' (S10,NBT)  
All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp  
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources

(K02) DNR monument  
11" Cedar N56E 21.76' (1/4S,NBT)  
7" Cedar S79E 20.50' (1/4S,NBT)  
11" Cedar S16E 11.28' (1/4S,NBT)  
10" Cedar N89W 13.57' (1/4S,NBT)  
All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.



Date August 28, 2012

20100

20102

Revised May 14, 1975  
Revised Jan., 1983  
Revised Oct., 1995