

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
Felch Township		
1. Public Land Survey	T 42N R 29W	K04
	T 42N R 29W	K05
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Jeremy J. Pipp, in a field survey on 8/02/2012AD do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K04) Quarter corner common to Sections 11 and 12. 1849: John Burt, DS. Set Hemlock  
post witnessed by Hemlock 9 S18W 19 links (12.54'), Lynn 18 N11E 35 links (23.10').

(K05) Corner common to Sections 11, 12, 13, and 14. 1849: John Burt, DS. Set Cedar post  
witnessed by Sugar 24 S57E 36 links (23.76'), Sugar 14 N71W 34 links (22.44').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K04) No evidence of original survey or subsequent restoration found. Corner position  
reestablished by single proportionate measurement between the Southeast corner and the  
Northeast corner of Section 11. Position is accepted as a careful and faithful  
REESTABLISHMENT of the position of the original corner.

(K05) No evidence of original survey or subsequent restoration found. Corner position  
reestablished by double proportionate measurement between Section Corners Two miles  
North, One mile East, One mile South, and Two miles West. Position is accepted as a  
careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K04) DNR monument  
5" Cherry N55E 9.10' (1/4S,NBT)  
6" Aspen S65E 9.07' (1/4S,NBT)  
4" Spruce S65W 25.76' (1/4S,NBT)  
5" Aspen N53W 6.32' (1/4S,NBT)

All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp  
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources

(K05) DNR monument  
9" Cherry N52E 16.22' (S12,NBT)  
9" Cherry S72E 26.46' (S13,NBT)  
9" Cherry S04W 45.72' (S14,NBT)  
10" Aspen N75W 13.17' (S11,NBT)

All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp Date August 28, 2012

**JEREMY J. PIPP**  
PROFESSIONAL SURVEYOR  
OFFICIAL SURVEY FACILITY  
50447

20107

20108

