

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 30W	J5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 14 T 44N R 30W	1
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 07/28/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11 and 14. 1970 - The corner was reestablished by A.O.Enger RLS proportionate to the original record between Section corners 39.923 ch. East and 39.912 ch. West. Set 1"IDx36" iron pipe with 4" aluminum cap. W.Birch 8" S85E 5.0', W.Birch 6" S21-1/2W 38.2'.

(1-Sec. 14) West 1/16 corner between Sections 11 and 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Found the 1970 monument in good condition and at record bearing and distance from the 1970 witnesses. The W.Birch SE is in good condition with overgrown blazes. The W.Birch SW is a dead stub. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(1-Sec. 14) Established the corner midway and on the Section line between Section corner 1316.57' west and Quarter corner 1316.57' east. The position for the corner falls in the westerly of the Floodwood Lakes and can not be monumented. Established a witness corner 160.00' west of the corner position and on the Section line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
18" W.Birch S81E 5.1' old blazes 1970 NBT
14" W.Pine N55E 37.0' mrkd "1/4S NBT"
8" W.Pine N86E 41.9' do
12" Tamarack S59W 40.7' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
160.00' West of the corner position and on the
Section line between Sections 11 and 14.
Set measuring nail with MDNR tag in the side of:
8" Y.Birch N71E 10.1' mrkd "WC BT"
8" Maple S17W 21.9' do
11" Maple S89W 10.65' do
5" Maple N30W 22.4' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/09/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

