

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 30W	D3
	T R	
	T R	
2. Property Controlling in Section	S T 44N R 30W	1
	S 8 T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 08/03/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D3) Quarter corner common to Sections 5 and 8. 1848 - Established by John Burt Deputy Surveyor
midway and on the Section line between Section corners 40.03 chains east and west. Set post.
Tamarack 16 N12W 28 links, Tamarack 7 N47W 71 links. Found no subsequent record.

(1-Sec. 8) West 1/16 corner between Sections 5 and 8. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D3) The original post and accessories were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the corner position midway and on the
Section line between Section corners 2671.79' east and west, proportionate to the original record.
The position for the corner falls in an open B.Spruce-Tamarack marsh. The monument was made firm
with spruce hubs driven adjacent.

(1-Sec. 8) Established the corner midway and on the section line between Section corner 1335.89' west
and Quarter corner 1335.90' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Tamarack N22E 20.85' mrkd "1/4S NBT"
8" Tamarack N61E 32.9' do
3" Tamarack N69W 36.45' do
10" Tamarack N36W 46.05' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" B.Spruce N22E 8.8' mrkd "1/16S BT"
8" B.Spruce S61E 22.9' do
12" W.Birch S89W 21.7' do
2" Cherry S54W 4.7' mrkd " X X "
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/09/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

