

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 30W	E4
	T 44N R 30W	C4
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E4 08/04/2010 C4 08/05/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E4) Quarter corner common to Sections 8 and 9. 1848 - Established by John Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set Maple post. Cedar 9 S41E 34 links, Sugar 14 S88W 37 links. Found no subsequent record.

(C4) Quarter corner common to Sections 7 and 8. 1980 - K.L.Sackett RLS reestablished the corner position at a found 1.5" iron pipe with squared scribed cedar post adjacent. 6" Sugar S71W 20.6', 8" Sugar N71E 19.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2633.43' north and south, proportionate to the original record. The position for the corner falls at the edge of a seasonal pool.

(C4) Found a 3/4" O.D. iron pipe with mushroomed top, set firm, and at record bearing and distance from the 1980 witness, both in good condition with double overgrown blazes. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 8" B.Ash S81E 18.6' mrkd "1/4S NBT" 6" Sugar S61W 15.7' do 7" Sugar N83W 14.7' do 10" Sugar N11W 33.7' do Set sq'd cedar post adjacent. Bearings are magnetic.

(C4) Fd. 3/4" O.D. iron pipe. Set measuring nail with MDNR tag in the side of: 10" Sugar N73E 19.5' old blazes 1980 NBT 8" Sugar S75W 20.85' do do 7" Sugar N16E 6.55' mrkd "1/4S NBT" 4" Sugar S19E 8.6' do Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/09/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

