

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 30W	E8
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/10/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20-21. 1848 - Established by John Burt Deputy Surveyor midway
and on the Section line between Section corners 40.00 chains north and south. Set cedar post.
Spruce 12 S10E 25 links, Spruce 12 N88W 18 links. 1934 field book notes of E.R.Nelson and
W.C.Johnson on file at Dickinson Co. Rd. Commission office show "squared cedar stake and iron pipe"
with NBTs 4" Poplar N12E 8.5', 5" Poplar N77E 27.3', 6" Poplar S15E 37.5'. 1941 - Corner shown on a
drawing prepared by Holland, Ackeman, and Holland for Wisconsin Michigan Power Company-Way Dam
Reservoir. 1 1/2" iron pipe set by County. Replaced with concrete monument. 5" Poplar N32W 5.2',
4" Poplar N55E 9.7', 5" Poplar S12W 8.1'. The distance from E8 to E9 is given on the drawing as
2614'. The distance between E8 and E7 is also given but it is not clear on the drawing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) The original post and accessories were not recovered. Found the Wisconsin Michigan Power
Company monument, a 7" square concrete monument with a 3" square brass cap stamped to identify the
corner, in good condition, with a 1-1/2" I.D. iron pipe, projecting 3' above ground, adjacent. None
of the 1934 or 1941 accessories were recovered. This monument was found to be 2614.02' north of
corner E8 or record. Accepted the monument as the best available evidence of the position of the
original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Found 7" square Wisconsin Michigan
Power Company concrete monument.
Set measuring nail with MDNR tag in the side of:
9" W.Spruce N49E 52.3' mrkd "1/4S NBT"
9" Balsam S65E 9.2' do
4" Poplar S33W 28.9' do
3" Poplar N20W 13.8' do
Set sq'd cedar post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 12/09/2010
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995