

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County)	Located In:	Corner Code #
1. Public Land Survey	T 44N R 30W	C3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 8 T 44N R 30W	4
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3		7	●	8		9		10		11		12	
4													
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on C3 08/05/2010
4 08/04/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1980 - K.L.Sackett RLS reestablished the corner position at
a found 1.5" iron pipe with very old squared post adjacent. 5" Spruce S85E 28.5', 4" Tamarack N29E
76.9', 4" Tamarack S38W 46.0'.

(4-Sec. 8) Northwest 1/16 corner, Section 8. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found a 1.5" O.D. iron pipe with threaded coupling on top, in good condition, and at record
bearing and distance from the 1980 witnesses. The 5" Spruce is dead and down, both 4" Tamaracks are
in good condition with scribing visible. Accepted the monument as the best available evidence of the
position of the original corner. Found an old squared wood post adjacent.

(4-Sec. 8) Established the corner at the intersection of straight lines connecting opposite 1/16
corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Fd. 1.5" O.D. iron pipe
Set measuring nail with MDNR tag in the side of:
4" Tamarack N34E 76.8' 1980 marks found
4" Tamarack S43W 46.4' do
3" B.Spruce N82E 17.5' mrkd "S5 NBT"
3" W.Pine S47E 26.5' "S8 NBT"
Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" W.Birch N80E 19.1' mrkd "1/16S BT"
8" Sugar S04W 13.9' do
10" Sugar S77W 31.1' do
8" Sugar N65W 9.9' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/09/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

